



Keysight

Santa Rosa, CA

CLIENT/OWNER

Keysight Technologies

GENERAL CONTRACTOR

Swinerton

DURATION

2 Months

COMPLETION DATE

August 2021

CONTRACT VALUE

\$3.4MM

PROJECT SUMMARY

Keysight Technologies consisted of the retrofit of the central utility plant (CUP) condenser water (CW) system serving the buildings of this campus. Initially, 1200 tons of temporary chillers were installed to facilitate the plant upgrades. The existing CW system was removed and upgraded with 6000 tons of new stainless cooling towers, centrifugal separator filtration skids, and sand filter system including modification of the CUP piping, including new 20" headers.

MARKET SECTORS

- Retrofit
- Commercial

SERVICES

- BIM/VDC
- Controls & Automation
- Engineering
- Mechanical
- Plumbing
- Special Projects